

INNOVATE, INTEGRATE, AUTOMATE

2 Jermyn Street Robertsham 2091, PO Box 7764 Weltevredenpark 1715

Tel: +27 11 680 0640, Fax: +27 11 680 0646

www.omegafs.co.za

	Client Details:			QUOTATION No: JA2018-Pick n Pay Lakefield-Fire Detection								
Contact Person: Haliem Vogt Company: Pick n Pay Cell: 076 022 3531 Tel: 021 658 1935 Fax:			Date: 21/02/2018 Sales Consultant: Jivesh Arjun Cell: 084 709 4142 email: jivesh@omegafs.co.za Rubeshen: 073 361 323 email: rubeshen@omegafs.co.za									
							email:	abdulhaliemvogt@pnp.co.za	Graham:	082 880	8659 email:	graham@foag.co.za
							Site	Pick n Pay - Lakefield				
							ITEM	Equipment Description	UNIT	QTY	RATE	TOTAL
1	Supply, Installation and Commission of Fire Detection System			-	_							
1.1	Ziton ZP2 Fire Panel	ea	1	9 887,41	9 887,41							
1.2	Ziton ZP2 Repeater Panel (item not added to total)	eu	'	5 683,23	7 007,41							
1.3	12V 7.2 AH	ea	2	291,76	583,52							
1.4	Series mini interface unit	ea	2	858,38	1 716,76							
1.5	Series mini relay unit, mains switching	ea	2	1 217,20	2 434,39							
1.6	Isolator base for seven series sensors	ea	2	789,69	1 579,38							
1.7	Surface mounting sensor base	ea	25	213,75	5 343,83							
1.8	Optical sensor	ea	24	553,44	13 282,63							
1.9	Heat sensor	ea	1	605,30	605,30							
1.10	Flush mounting red analogue callpoint with surface mounting box	ea	3	640,25	1 920,76							
1.11	Omnidirectional sounder & indicator with mounting base	ea	5	1 295,98	6 479,89							
1.12	Surface box for A Series modules,	ea	2	347,37	694,73							
1.13	Fire Retardant Cable 2 X 1mm.sq PH30	per m	500	16,60	8 300,00							
1.14	LED indicator for ceiling void	ea	4	200,39	801,54							
1.15	20mm Epoxy Coated Bossal Piping	per m	20	125,75	2 515,00							
1.16	50mm Steel Cable Ties	lot	1	278,50	278,50							
1.17	20mm Steel Sprag	per m	20	96,50	1 930,00							
				-	-							
2	<u>PnGs</u>			-	-							
2.1	Design, Installation and Commission	lot	1	6 000,00	6 000,00							
2.2	Training and Handover Documentation	lot	1	3 000,00	3 000,00							
2.3	Travel	per km	400	4,50	1 800,00							
2.4	Sundries	lot	1	750,00	750,00							
				-	-							
				-	-							
3	<u>Notes</u>			-	-							
3.1	The above BOQ is generated from the drawings supplied by the client			-	-							
3.2	The installation and commission of the system will be compliant to SANS10139 Regulations			-	-							
3.3	Optical sensors have been added for the ceiling void in the admin area.			-	-							
3.4	The fire panel will be mounted in an area that is manned. Should the client require the main fire panel to be mounted in an an office, a repeater panel (Item 1.2) can be added to the total BOQ.			-	-							
				<u>-</u>	-							
	Sub-Total Excl VAT:			-	R 69 903,64							
	VAT:			-	R 9 786,51							
	Total Incl VAT			-	R 79 690,15							
				_	-							
				_	_							
			<u> </u>		<u> </u>							

Order / Reference No. :	Date
Acceptance: (Full Name)	Signature:
E&OE	
Omega Fire and Security reserves the right to retake possession	of all equipment not paid for completely within the payment term set out above
All goods / equipment remain the property Omega Fire and Se	curity until paid for completely.
All pricing quoted, is subject to the exchange rate variations.	
Delivery: 1 - 6 Weeks, subject to stock availability.	
Payment Terms: COD / 30 Days on approved accounts.	
Validity: Quote valid subject to rate of exchange (30days)	